ANDERSON REGIONAL
JOINT WATER SYSTEM

INVITATION TO BID

Project: **ALUM SLUDGE DREDGING**

Owner: **ANDERSON REGIONAL JOINT WATER SYSTEM**

Sealed bids for the Alum Sludge Dredging project for the Anderson Regional Joint Water System (ARJWS) will be received until 2:00 p.m. EDT, Thursday June 12, 2025, at its office located at 998 Hunters Trail, Anderson, SC 29625.

ARJWS owns and operates two (2) sludge lagoons in series. The upper lagoon captures most of the solids and decants to the lower lagoon; therefore, the primary removal will take place in the upper lagoon. Each lagoon is approximately 2 acres in size and 14 feet deep.

Utilities: Owner will supply one electrical service hook up (480V/3Ph/60A) and 2in potable water connection (50 psi min).

Project Description: The work to be performed shall consist of furnishing all NSF- certified materials, tools, equipment, and labor necessary for removing solids from the water treatment plant lagoon(s), dewatering the material, and transporting it to a designated facility for disposal. Estimated quantity is 600 dry tons. Prepare a representative sample of dewatered solids daily and deliver to the owner. Owner will perform percent solids analysis and pay disposal fees directly to the landfill (Anderson Regional Landfill).

Payment: Shall be based on actual quantities removed and contractor shall provide an invoice not less than monthly.

Notice to Proceed is expected to be issued in July 2025

Insurance certificate minimum of one (1) million dollars general liability is required. Coverage shall remain in force, at all times, during the term of the contract at the bidder's sole expense.

The Owner reserves the right to waive any informalities, or to reject any or all bids, and to award the contract to the best and most responsible bidder.

No bidder may withdraw his bid within 60 days after the opening thereof.

All bids should be submitted using the attached bid form. Bids may be submitted in a sealed envelope bearing on the outside the name of the Bidder, address, and name of the project or via email to Bgood@arjwater.com. Envelopes containing bids must be addressed as follows, and delivered to:

Brandon Good, Operations Superintendent
Anderson Regional Joint Water System
998 Hunters Trail, Anderson, SC 29625

RE: ALUM SLUDGE DREDGING
BID ENCLOSED

All requests for additional information shall be submitted by email prior to 5:00 p.m. on June 2, 2025, to Bgood@arjwater.com. Requests will be answered on June 3, 2025.

ANDERSON REGIONAL
JOINT WATER SYSTEM

BID FORM

Project: **Alum Sludge Dredging**

Description: **The work to be performed shall consist of furnishing all materials, tools, equipment, and labor necessary for removing solids from the water treatment plant lagoon(s), drying the material, and transporting it to a designated facility for disposal.**

Date: **June 12, 2025**

Item	Description	Units	Unit Cost
1	Mobilization	Each	
2	Sludge Removal, Dewatering, Handling	Dry Tons	
3	Remobilzation (Onsite Only)	Each	
4	Demobilization	Each	

By: _____

Print: _____

Title: _____

Company: _____